

SN1101-A1	<b>Station Service Voltage Transformers (SSVT)</b> <b>Specification</b> <b>Specific Requirements (Data to be supplied by Entergy)</b>	Rev No 02
-----------	---	-----------

1	Substation	Bayou Labutte
2	Quantity required	1
3	Date required	01/04/2024
4	Nominal System Voltage (See 6.1.3) <input type="checkbox"/> 500 kV, <input type="checkbox"/> 345 kV, <input checked="" type="checkbox"/> 230 kV, <input type="checkbox"/> 161 kV, <input type="checkbox"/> 138 kV, <input type="checkbox"/> 115 kV, <input type="checkbox"/> 69 kV	230kV
5	Primary Winding Voltage (see 6.1.3) <input type="checkbox"/> 287.5 kV, <input type="checkbox"/> 207 kV, <input checked="" type="checkbox"/> 138 kV, <input type="checkbox"/> 92 kV, <input type="checkbox"/> 80.5 kV, <input type="checkbox"/> 69 kV, <input type="checkbox"/> 40.25 kV	138kV
6	Secondary Winding Voltage (see 6.1.3) <input checked="" type="checkbox"/> 125/250 V, <input type="checkbox"/> 277 V, <input type="checkbox"/> 480 V, <input type="checkbox"/> Other _____,	125/250 V
7	Rated Load (See 6.1.5) <input type="checkbox"/> 50 kVA, <input type="checkbox"/> 100 kVA, <input checked="" type="checkbox"/> Other 167 kVA	167kVA
8	Metering Winding (see 6.1.8)	Required/ <del>Not required</del>
9	Metering winding voltage (See 6.1.8)	Per spec /other N/A
10	Metering Winding Accuracy (See 6.1.8)	N/A
11	Insulator Creepage Distance (See 6.2.1.5)	Per spec /other 230 inches
12	Primary fault detection CT (See 6.2.5.2)	Required/ <del>Not required</del>
13	Secondary fault detection CT (See 6.2.5.1)	Required/ <del>Not required</del>
14	Mounting Support Pedestal (see 6.2.4.1)	Required/ <del>Not required</del>
15	Mounting Pedestal drawing;	N/A
16	Point of Delivery	54780 Dean Road, Plaquemine, LA 70764
17	Person(s) to notify 48 hours in advance of shipment	Cory Spoonmore 504.576.3573
19	Send test reports to	Cory Spoonmore
20	Send drawings and instruction manuals to	639 Loyola Ave., New Orleans, LA 70113
21		
22		